CCS NATIONAL INSTITUTE OF AGRICULTURAL MARKETING (An organization of Ministry of Agriculture and Farmers Welfare) Kota Road, Bambala, Pratap Nagar, Jaipur-302033

S.NO. E- File no 128262, 02/NIAM/Admin/2021-2023/ 130440

DATED 09.09.2025

Short Term NIT Notice

The Director General CCS NIAM invites Short term/limited tender for "repair of road at main gate and painting of sentry hut at CCS NIAM Jaipur from the approved and eligible contractors of CPWD/MES/RAJASTHAN STATE PWD/PSU From Central Govt./State Govt. The interested agencies may submit their sealed quotations in the prescribed format in the office of Director General office till 23.09.2025 upto 3.00 PM. The description of work are as under:

S.No	Description of items	Quantity	Unit	Rate	Amount
1	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: a) bituminous road	110	Sqm		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	5	Cum		
3	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm/40 mm nominal size as required at site) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	10	Cum		
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. a) With cement mortar 1:4 (1cement: 4 coarse sand)	25	Sqm		
5	the second putter	75	Sqm		

Sypter



	manufacturer, over the plastered wall surface to	and a supplied to the supplied	The second secon	
6	wall painting with premlum acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.	75	Sqm	
7	a) Two or more coats Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	75	Sqm	
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: a) Two or more coats on old work	75	Sqm	
9	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. a) Fixed to openings /wooden frames with rawl plugs screws etc.	35	Kg	
10	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	35	Kg	
11	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses		Sqm	

	and including cutting to size and shape wherever required.			
12	Supplying and applying one water proofing coat on terrace of average thickness 1 mm, of approved brand and manufacturer, over the plastered surface.	25	Sqm	
	Total			

General conditions and specifications for civil work

- 1. The estimated cost of the work is Rs. 1,97,589/-
- 2. The time allowed for completion of the work will be 45 Days from the date of award of work.
- 3. The work shall be carried out in accordance with the CPWD Specifications 2019 Vol. I to II (corrected up to the last date of submission/uploading of bid) hereinafter referred as CPWD Specifications.
- 4. The Agency shall remove from site all rubbish and debris generated during the works and keep site clean and tidy throughout the Contract Period. All the serviceable and non-serviceable (malba) material shall be segregated and stored separately. Malba, rubbish & other waste materials shall be disposed of as directed by Infra Committee.
- 5. All serviceable material shall be kept in safe custody of the Institute as per direction of Infra Committee.
- 6. Defect liability period is 6 months after date of completion of the work.
- 7. As a guarantee towards due performance and compliance of the contract work, the successful bidder (contractor) will deposit an amount equal to 5% of contract value and should be kept valid for a period of 6 months beyond completion of all the contractual obligation as security deposit by way of demand draft in favour of Director General "NATIOANL INSTITUTE OF AGRICULTURAL MARKETING" payable at JAIPUR drawn on any Nationalized Bank/Scheduled Bank and payable at JAIPUR within ten days of the issue of the Letter of notification of award.
- 8. The contractor shall get the shades of all types of paints, distemper, water proofing cement paint etc. approved from the Infra -in-charge before procurement of materials.
- 9. The work will be executed as per satisfaction of the Infra committee.
- 10. The quotation will be submitted in the prescribed format.
- 11. The agency will submit GST certificate with the quotation.
- 12. The agency will submit bill in 2 copies in the office after completion of work for payment.

Assistant Director (Infra)